

Subdivisional Lines of T. 4 N., R. 32 E., W.M.

Chains		Feet
	E. on random bet. Secs. 23 & 26, T. 4 N., R. 32 E.	
40.00	Set temp. $\frac{1}{4}$ Sec. post	
79.83	Intersect N. & S. line, 20 lks. N. of post, from which I run	
	N. $89^{\circ} 51'$ W. on true line	
39.91	Set $\frac{1}{4}$ Sec. post in head of small gully, sloping N.E.	
79.83	To post Cor.	
	Land; rolling	
	Grass good	
	Soil; 2nd rate.	
<hr/>		
	N. bet. Secs. 22 & 23, T. 4 N. R. 32 E.	
		Var. $20^{\circ} 30'$ E.
40.00	Set $\frac{1}{4}$ Sec. post; drove charred stake, dug pits and raised mound as per instructions.	
45.00	To top of hill	
56.00	Ravine, water standing in holes, course W.	
80.00	Set post Cor. for Secs. 14, 15, 22 & 23; drove charred stake, dug pits and raised mound as per instructions.	
	Land; rolling	
	Grass good	
	Soil; 2nd rate.	
<hr/>		
	E. on random bet. Secs. 14 & 23, T. 4 N., R. 32 E.	
40.00	Set temp. $\frac{1}{4}$ Sec. post	
79.50	Intersect N. & S. line at post, from which I run	
	W. on true line	
39.75	Set $\frac{1}{4}$ Sec. post; drove charred stake, dug pits and raised mound as per instructions.	
79.50	To post Cor.	
	Land; broken	
	Soil; 2nd rate.	
	Grass good.	
<hr/>		