

## Subdivisional Lines of T. 4 N., R. 32 E., W.M.

Chains		Feet
	N. bet. Secs. 14 & 15, T 4 N R 32 E	
		Var. 20° 30' E.
40.00	Set $\frac{1}{4}$ Sec. post, drove charred stake, dug pits and raised mound as per instructions.	
80.00	Set Post Cor. for Secs. 10, 11, 14 & 15; drove charred stake, dug pits and raised mound as per instructions.	
	Land; rolling	
	Good grass	
	Soil; 2nd rate.	
<hr/>		
	E. on random bet. Secs. 11 & 14, T. 4 N R. 32 E.	
40.00	Set temp. $\frac{1}{4}$ Sec. post	
80.00	Intersect N. & S. line at post from which I run	
	W. on true line	
40.00	Set $\frac{1}{4}$ Sec. post; drove charred stake, dug pits and raised mound as per instructions.	
80.00	To post Cor.	
	Land; rolling, good grass	
	Soil; 2nd rate.	
<hr/>		
	N. bet. Secs. 10 & 11, T 4 N R 32 E	
		Var. 20° 30' E
40.00	Set $\frac{1}{4}$ Sec. post; drove charred stake, dug pits and raised mound as per instructions.	
80.00	Set post Cor. for Secs. 2, 3, 10 & 11; Drove charred stake dug pits & raised mound as per instructions.	
	Land; rolling, grass good	
	Soil; 2nd rate.	
<hr/>		
	E. on random bet. Secs. 2 & 11, T 4 N R 32 E.	
40.00	Set temp. post	
79.60	Intersect N. & S. line, 40 lks. S. of post, from which I run	
	S. 89° 43' W.	
39.80	Set $\frac{1}{4}$ Sec. post; drove charred stake, dug pits and raised mound as per instructions.	