

Subdivisional Lines of T. 4 N., R. 32 E., W.M.

Chains		Feet
	Land; rolling, grass good Soil; 2nd rate.	
	<hr/>	
	N. bet. Secs. 27 & 28, T 4 N R 32 E	
		Var. 20° 45' E
40.00	Set $\frac{1}{4}$ Sec. post in side hill, sloping to N.E.; drove charred stake, dug pits and raised mound as per instructions.	
46.00	To Ravine	
80.00	Set post Cor. for Secs. 21, 22, 27 & 28, on side hill sloping to the N.E.	
	Land; rolling, grass good Soil; 2nd rate.	
	<hr/>	
	E. on random bet. Secs. 22 & 27, T 4 N R 32 E	
40.00	Set temp. $\frac{1}{4}$ Sec. post.	
79.35	Intersect N. & S. line, 16 lks. S. of post, from which I run	
	S. 89° 53' W. on a true line	
39.67	Set $\frac{1}{4}$ Sec. post in W. side of ravine, course N.	
79.35	To post Cor.	
	Land; rolling Grass good Soil; 2nd rate.	
	<hr/>	
	N. bet. Secs. 21 & 22, T 4 N R 32 E	
		Var. 21° E
40.00	Set $\frac{1}{4}$ Sec. post; drove charred post, dug pits and raised mound as per instructions.	
80.00	Set post Cor. for Secs. 15, 16, 21 & 22; drove charred stake dug pits and raised mound as per instructions.	
	Land; rolling, grass good Soil; 2nd rate.	
	<hr/>	
	E. on random bet. Secs. 15 & 22, T 4 N. R 32 E.	
40.00	Set temp. $\frac{1}{4}$ Sec. post.	