

Subdivisional Lines of T. 4 N., R. 32 E., W.M.

Chains		Feet
79.75	Intersect N. & S. line, 70 lks. N. of post from which I run	
	N. 89° 30' W. on true line	
39.87	Set $\frac{1}{4}$ Sec. post; drove charred stake, dug pits and raised mound as per instructions.	
79.75	To post Cor.	
	Land; rolling	
	Grass good	
	Soil; 2nd rate.	
<hr/> N. bet. Secs. 28 & 29, T 4 N R 32 E May 4, 1865		
		Var. 20° 30' E
40.00	Set $\frac{1}{4}$ Sec. post; drove charred stake, dug pits and raised mound as per instructions.	
80.00	Set post Cor. for Secs. 20, 21, 28 & 29, on side hill sloping to the S.; drove charred stake, dug pits and raised mound as per instructions.	
	Land; rolling, grass good	
	Soil; 2nd rate.	
<hr/> E. on random bet. Secs. 21 & 28, T 4 N R 32 E		
40.00	Set temp. $\frac{1}{4}$ Sec. post	
79.50	Intersect N. & S. line, 50 lks. N. of post, from which I run	
	N. 89° 39' W. on true line	
39.75	Set $\frac{1}{4}$ Sec. post on E. side of hill; drove charred stake, dug pits and raised mound as per instructions.	
79.50	To post Cor.	
	Land; broken	
	Soil; 2nd rate.	
	Grass good	
<hr/> N. bet. Secs. 20 & 21, T 4 N R 32 E		
		Var. 20° 45' E.
40.00	Set $\frac{1}{4}$ Sec. post, on side hill sloping to the N.	