

Subdivisional Lines of T. 4 N., R. 32 E., W.M.

Chains		Feet
	W. on random bet. Secs. 6 & 7, T 4 N R 32 E	
40.00	Set temp. $\frac{1}{4}$ Sec. post	
79.60	Intersect N. & S. T. line, 20 lks. N. of post from which I run	
	N. $89^{\circ} 34'$ E. on true line	
39.60	Set $\frac{1}{4}$ Sec. post; drove charred stake, dug pits and raised mound as per instructions.	
79.60	To post Cor. Land; rolling Grass good Soil; 2nd rate.	
N. bet. Secs. 5 & 6, T 4 N R 32 E		
		Var. $20^{\circ}30'E.$
40.00	Set $\frac{1}{4}$ Sec. post; drove charred stake, dug pits and raised mound as per instructions	
72.00	Intersect First Standard Parallel, 25 lks. E. of post Cor. for Secs. 31 & 32, T 5 N R 32 E. Set Closing Cor. post for Secs. 5 & 6; drove charred stake, dug pits and raised mound as per instructions. Land; rolling Grass good Soil; 2nd rate.	
General Description		
The lands in this Tp. are well adapted to grazing, excepting a scarcity of water, which can be remedied by sinking wells. The soil is uniformly rich and would be productive were the seasons less dry.		