

## Subdivisional Lines of T. 4 N., R. 33 E., W.M.

Chains		Feet
40.00	Set $\frac{1}{4}$ Sec. post, drove charred stake, dug pits & raised mound as per instructions.	
80.00	Set post cor. for secs. 1, 2, 11 & 12. Drove charred stake dug pits, raised mound as per instructions. Land; rolling, good grass. Soil; 2nd rate.	
<hr/> E. on random bet. Secs. 1 & 12, T. 4 N., R. 33 E.		
40.00	Set temp. post for $\frac{1}{4}$ Sec.	
79.91	Intersect N. and S. line, 25 lks. S. of post, from which I run, S. 89° 9' W. on true line	
39.94	Set $\frac{1}{4}$ Sec. post, drove charred stake, dug pits & raised mound as per instructions.	
79.91	To post cor. Land; rolling, good grass. Soil; 2nd rate.	
<hr/> N. on Random bet. Secs. 1 & 2, T 4 N R 33 E - Var. 21° E.		
40.00	Set temp. $\frac{1}{4}$ Sec. post.	
69.50	Intersect Standard Parallel, 6.50 W. of post, set C. Cor. post for Secs. 1 & 2. Drove charred stake, dug pits & raised mound as per instructions, from which I run S. on true line.	
29.50	Set $\frac{1}{4}$ Sec. post, drove charred stake, dug pits & raised mound as per instructions.	
69.50	To post cor, Land; rolling, grass good Soil; 2nd rate.	
<hr/> April 26, 1865		
N. bet. Secs. 34 & 35, T. 4 N., R. 33 E.		
40.00	Set $\frac{1}{4}$ Sec. post, drove charred stake, dug pits & raised mound as per instructions.	