

Subdivisional Lines of T. 4 N., R. 33 E., W.M.

Chains		Feet
	Land; rolling, grass good Soil; 2nd rate.	
	N. bet. Secs. 21 & 22, T. 4 N., R. 33 E. Var. 21° E.	
40.00	Set $\frac{1}{4}$ Sec. post, drove charred stake, dug pits & raised mound as per instructions.	
80.00	Set post Cor. for Secs. 15, 16, 21 & 22; drove charred stake dug pits & raised mound as per instructions. Land; gently rolling, grass good Soil; 2nd rate.	
	E. on random bet. Secs. 15 & 22, T. 4 N., R. 33 E.	
40.00	Set temp. $\frac{1}{4}$ Sec. post	
79.70	Intersect N. and S. line at post, from which I run W. on true	
39.85	Set $\frac{1}{4}$ Sec. post; drove charred stake, dug pits & raised mound as per instructions.	
79.70	To post cor. Land; rolling, grass good Soil; 2nd rate.	
	N. bet. Secs. 15 & 16, T. 4 N., R. 33 E. Var. 21° E.	
40.00	Set $\frac{1}{4}$ Sec. post; drove charred stake, dug pit & raised mound as per instructions.	
80.00	Set post cor. for secs. 9, 10, 15 & 16; drove charred stake, dug pits and raised mound as per instructions. Land; broken good grass Soil; 2nd rate.	
	April 29, 1865	
	E. on random bet. Secs. 10 & 15, T. 4 N., R. 33 E.	
40.00	Set temp. $\frac{1}{4}$ Sec. post	
80.00	Intersect N. and S. line, 25 lks. N. of post, from which I run	