

Subdivisional Lines of T. 4 N., R. 33 E., W.M.

Chains		Feet
	S. 89° 49' W. on true line	
40.00	Set $\frac{1}{4}$ Sec. post; drove charred stake, dug pits & raised mound as per instructions.	
80.00	To post Cor. Land; rolling, grass good Soil; 2nd rate.	
N. bet. Secs. 9 & 10, T. 4 N., R. 33 E.		
Var. 21° E.		
40.00	Set $\frac{1}{4}$ Sec. post; drove charred stake, dug pits & raised mound as per instructions.	
80.00	Set post cor. for Secs. 3, 4, 9 & 10; drove charred stake dug pits, and raised mound as per instructions. Land; broken, grass good Soil; 2nd rate.	
E. on random bet. Sec. 3 & 4, T. 4 N., R. 33 E.		
40.00	Set temp. $\frac{1}{4}$ Sec. post	
79.63	Intersect N. and S. line, 23 lks. N. of post, from which I run N. 89° 40' W. on true line.	
39.81	Set $\frac{1}{4}$ Sec. post; drove charred post, dug pits and raised mound as per instructions.	
79.13	To post cor. Land; rolling, grass good Soil; 2nd rate.	
N. bet. Secs. 3 & 4, T. 4 N., R. 33 E.		
Var. 21° E.		
40.00	Set $\frac{1}{4}$ Sec. post; drove charred stake, dug pits and raised mound as per instructions.	
69.75	Intersect First Standard Parallel, 6.50 W. of Standard Cor., set post for C. Cor. for secs. 3 & 4. Land; broken, grass good Soil; 2nd rate.	