

Subdivisional Lines of T. 4 N., R. 33 E., W.M.

Chains		Feet
70.20	<p>To 1st Standard Parallel N. 6.84 chs. W. of Standard Cor. for sections. 32 & 33, T. 5 N., R. 33 E.; set post C. Cor. for secs. 4 & 5, T. 4 N., R. 33 E.; drove charred stake, dug pits and raised mound as per instructions.</p> <p>Land; broken</p> <p>Soil; 2nd rate.</p> <p>Good grass.</p>	
<hr/> <p>N. bet. Secs. 31 & 32, T. 4 N., R. 33 E.</p>		
<p style="text-align: right;">Var. 21° E.</p>		
40.00	<p>Set $\frac{1}{4}$ Sec. post; drove charred stake, dug pits & raised mound as per instructions.</p>	
80.00	<p>Set post Cor. for secs. 29, 30, 31 & 32; drove charred stake, dug pits and raised mound as per instructions.</p> <p>Land; rolling, grass good</p> <p>Soil; 2nd rate.</p>	
<hr/> <p>E. on random bet. Secs. 29 & 32, T. 4 N., R. 33 E.</p>		
40.00	<p>Set temp. $\frac{1}{4}$ Sec. post</p>	
79.10	<p>Intersect N. and S. line at post, from which I run W. on true line</p>	
39.55	<p>Set $\frac{1}{4}$ Sec. post; drove charred stake, dug pits & raised mound as per instructions.</p>	
79.10	<p>To post cor.</p> <p>Land; broken, grass good</p> <p>Soil; 2nd rate.</p>	
<hr/> <p>N. bet. Secs. 29 & 30, T. 4 N., R. 33 E.</p>		
<p style="text-align: right;">Var. 21° E.</p>		
40.00	<p>Set $\frac{1}{4}$ Sec. post; drove charred stake, dug pits & raised mound as per instructions.</p>	
80.00	<p>Set post cor. for secs. 19, 20, 29 & 30; drove charred stake, dug pits and raised mound as per instructions.</p> <p>Land; broken, grass good</p> <p>Soil; 2nd rate.</p>	