

Subdivisional Lines of T. 4 N., R. 33 E., W.M.

Chains		Feet
	S. 89° 35' E. on true line	
35.92	Set $\frac{1}{4}$ sec. Post; drove charred stake, dug pits & raised mound as per instructions.	
75.92	To post cor. Land; rolling, grass good Soil; 2nd rate.	
<hr/>		
	W. on random bet. Secs. 7 & 18, T. 4 N., R. 33 E.	
40.00	Set temp. $\frac{1}{4}$ Sec. Post	
75.47	Intersect N. and S. from line, 50 lks. S. of post, from which I run S. 89° 69' E. on true line	
35.67	Set $\frac{1}{4}$ Sec. Post; drove charred stake, dug pits and raised mound as per instructions.	
75.67	To Post cor. Land; broken, grass good Soil; 2nd rate.	
<hr/>		
	W. on random bet. Secs. 6 & 7, T 4 N., R. 33 E.	
40.00	Set temp. $\frac{1}{4}$ Sec. post	
75.25	Intersect N. and S. line, 3 lks. S. of cor. post, from which I run, S. 89° 59' E. on true line.	
35.25	Set $\frac{1}{4}$ Sec. post; drove charred stake, dug pits and raised mound as per instructions.	
75.25	To post cor. Land; broken, grass good Soil; 2nd rate.	
<hr/>		
Gen. Description		
<hr/>		
The land in this Tp. is well set to grazing, making them very desirable for stock raising.		
<hr/>		