

Exterior Bdy. of T. 3 N., R. 35 E., W.M. (W.Bdy.)

Chains		Feet
	N. on W. Bdy. of Sec. 30 Var. 21°30' E.	
40.00	Set post and made mound of earth for $\frac{1}{4}$ Sec. Cor.	
80.00	Set post and made mound of earth for Cor. to Secs. 30, 25, 19 & 24 Land; rolling Soil; good, good grass.	
	N. on W. Bdy. of Sec. 19 Var. 20° E.	
24.50	To wild Horse Creek, The N. Bdy. of the Indian Reservation.	
	Exterior Bdy. of T. 4 N., R. 34 E., W.M. As surveyed by Jas. P. Currin & Jas. E. Noland, U.S. Dep. Surv. Under their special Contract Dated May 4, 1887	
	Commencing on line bet. Tps. 4 N., R. 34 & 35 E. at Cor. to Secs. 13, 18, 19 & 24, which is a basalt stone buried in the ground (Initial Point to all surveys in vicinity) Thence I run S. on true line on E. Bdy. of Sec. 24 Var. 20° E.	
55.50	Across field T W.R. Bdy., set a basalt stone, 12 x 6 x 4 ins., 8 ins. in ground for meander cor. to secs. 19 & 24. Dug pit 3 ft. sq., 1 ft. deep, S. of stone, 8 lks. dist.; raised mound of earth, 2 ft. high, 4 $\frac{1}{2}$ ft. base alongside, mark- ed stone, W.R.M.C.	
56.25	Wild Horse Creek, 5 lks. Wide, course W.	
60.50	Walla Walla branch, R.R., course W.	
61.75	Wagon Road, course W. & E.	
62.25	Enter field	
80.00	Found old pits and mound for Cor. to Secs. 24, 25, 19 & 30, redug pits, set post, 48 x 4 x 4 ins., 12 ins. in the ground, marked T. 4 N., S. 24 on N.W., R. 35 E. S 19 on N.E., S. 30 on S.E. R. 34 E. S. 25 on S.W. with	