

## Exterior Bdy. of T. 4 N., R. 34 E., W. M.

Chains		Feet
40.00	Deposited a charred stake, 12 ins. in the ground for $\frac{1}{4}$ Sec. Cor., dug pits, 18 x 18 x 12 ins. N. & S. for Cor. $5\frac{1}{2}$ ft. dist., and raised a mound of earth $1\frac{1}{2}$ ft. high, $3\frac{1}{2}$ ft. base over it, in N. pit, drove a stake, 2 ft. long, 2 ins. sq., 12 ins. in the ground, marked $\frac{1}{4}$ S. on W. face.	
60.00	Deposited charred stake, 12 ins. in the ground for 1/16 Sec. cor., dug pits 18 x 18 x 12 ins. 6 W. of Cor., $5\frac{1}{2}$ ft. dist., raised a mound of earth, $1\frac{1}{2}$ ft. high, $3\frac{1}{2}$ ft. base over it. In E. pits, drove stake, 2 ft. long 2 ins. sq., 12 ins. in the ground, marked 1/16 S. in W. face.	
79.00	Road, course, N. & S.	
80.00	Set a post, 54 x 4 x 4 ins., 12 ins. in the ground for Cor. to Tps. 3 & 4 N., R. 34 & 35 E., marked T. 4 N., R. 34 E., S. 36 on N.W., R. 35 E., S. 31 on N.E. T 3 N., S. 6 on S.E., S. 1 on S.W., with 6 notches on each edge, dug pits, 24 x 18 x 12 ins. lengthwise on each line, N.S.E. & W. of post, 6 ft. dist. & raised a mound of earth, $2\frac{1}{2}$ ft. high, 5 ft. base around post. Land; level Soil; 1st rate, some grass.	
Subdivisional Lines of T. 4 N., R. 34 E., W.M. As surveyed by Wm. H. Odell, U.S. Deputy Surveyor. Under Contract No. 114 Dated July 2nd, 1866.		
Subdivision commenced July 31, 1866 From the Cor. to Secs. 1, 2, 35 & 36, on the S. Bdy. of the Tp. I run N. bet. Secs. 35 & 36		
40.00	Set post Cor. for $\frac{1}{4}$ Sec.; drove charred stake; dug pits; and raised mound as per instructions.	
80.00	Set post Cor. for Secs. 25, 26, 35 & 36, drove charred stake, dug pits; and raised mound as per instructions. Land; gently rolling, good grass	