

Subdivisional Lines of T. 4 N., R. 34 E., W.M.

Chains		Feet
	E. on random bet. Secs. 1 & 12 Var. 20° E.	
40.00	Set temp. $\frac{1}{4}$ Sec. post Cor.	
80.56	Intersect N. & S. line, 40 lks. N. of post Cor. N. 89° 43' W. on true line	
40.28	Set $\frac{1}{4}$ Sec. post Cor.; drove charred stake, dug pits and raised mound as per instructions.	
80.56	To post Cor. Land; broken, good grass. Soil; 2nd rate.	
<hr/>		
	N. bet. Secs. 1 & 2	
40.00	set post Cor. for $\frac{1}{4}$ Sec.; drove charred stake, dug pits and raised mound as per instructions.	
69.46	Intersect 1st Standard N. 5.94 chs. W. of Standard Cor. for Secs. 36 & 35, T. 5 N., R. 34 E.; set Closing Cor. for Secs. 1 & 2, at intersection; drove charred stake, dug pits and raised mound as per instructions. Land; broken, covered with good grass. Soil; 2nd rate. August 1st, 1866	
<hr/>		
	N. bet. Sec. 34 & 35	
40.00	Set post Cor. for $\frac{1}{4}$ Sec.; drove charred stake, dug pits, and raised mound as per instructions.	
60.75	Wild Horse Creek, 10 lks. wide, course N.W.	
61.00	Enter field	
67.00	Leave field, course of fence, E. & W.	
80.00	Set post Cor. for Secs. 26, 27, 34 & 35; drove charred stake, dug pits, and raised mound as per instructions. Land; level, Soil; 1st rate. Somewillow along the banks of the creek. There is a small grove of Cottonwood timber, just below the line. Mr. Edwards house brs. S. 50° W., from Cor., about 25 Chs.	
<hr/>		
	E. on random bet. Secs. 26 & 35 Var. 20° E.	
40.00	Set temp. $\frac{1}{4}$ Sec. post Cor.	
79.60	Intersected N. & S. line, 30 lks. S. of post Cor. S. 89° 47' W. on true line	
39.80	Set $\frac{1}{4}$ Sec. post Cor.; drove charred stake, dug pits and raised mound as per instructions.	
52.10	Wild Horse Creek, 10 lks. Wide, course S.W.	