

## Subdivisional Lines of T. 4 N., R. 34 E., W.M

Chains.		Feet
	and raised mound as per instructions.	
80.20	To post Cor. Land; 2nd rate.	
	N. bet. Secs. 14 & 15	
40.00	Set post Cor. for $\frac{1}{4}$ Sec.; drove charred stake, dug pits and raised mound as per instructions.	
80.00	Set post Cor. for Secs. 10, 11, 14 & 15; drove charred stake, dug pits and raised mound as per instructions. Land; rolling Soil; 2nd rate.	
	E. on random bet. Secs. 11 & 14	
40.00	Set temp. $\frac{1}{4}$ Sec. post Cor. Var. 20° E.	
80.26	Intersect N. & S. line, 15 lks. S. of post. S. 89° 54' W. on true line	
40.13	Set post Cor. for $\frac{1}{4}$ Sec. Cor.; drove charred stake, dug pits and raised mound as per instructions.	
80.26	To post Cor. Land; broken, good grass. Soil; 2nd rate.	
	N. bet. Secs. 10 & 11	
40.00	Set post Cor. for $\frac{1}{4}$ Sec.; drove charred stake, dug pits, and raised mound as per instructions.	
80.00	Set post Cor. for Secs. 2, 3, 10 & 11; drove charred stake, dug pits, and raised mound as per instructions. Land; rolling, good grass. Soil; 2nd rate.	
	E. on random bet. Secs. 2 & 11	
40.00	Set temp. $\frac{1}{4}$ Sec. post Cor. Var. 20° 30' E.	
80.22	Intersect N. and S. line, 19 lks. S. of post Cor. S. 89° 52' W. on true line	
40.11	Set post Cor. for $\frac{1}{4}$ Sec.; drove charred stake, dug pit and raised mound as per instructions.	
80.22	To post Cor. Land; rolling, good grass. Soil; 2nd rate.	