

Subdivisional Lines of T. 4 N., R. 34 E., W.M.

Chains		Feet
	at	
80.50	Intersect E. Bdy. T., 75 lks N. of Cor. to Secs. 25, 36, 30 and 31, thence N. 89° 28' W. on true line	
	Var. 20 $\frac{1}{4}$ ° E.	
20.50	Deposited charred stake, 12 ins. in the ground for 1/16 Sec. Cor.; dug pits, 18 x 18 x 12 ins. E. and W. of stake, 5 $\frac{1}{2}$ ft. dist, raised mound of earth, 1 $\frac{1}{2}$ ft. high, 3 $\frac{1}{2}$ ft. base over it and in E. pit, drove stake, 2 ft. long, 2 ins. sq., & 2 ins. in the ground marked: 1/16 S. on N. face.	
40.50	Set post, 3 ft. long, 3 ins. sq., 24 ins. in the ground for $\frac{1}{4}$ Sec. Cor., marked $\frac{1}{4}$ on N. face, dug pits 18 x 18 x 12 ins. E. and W. of post 5 $\frac{1}{2}$ ft. dist. and raised mound of earth 1 $\frac{1}{2}$ ft. high, 3 $\frac{1}{2}$ ft. base around it.	
60.20	Wire fence, course E, and W.	
60.50	Deposited charred stake, 12 ins. in the ground for 1/16 Sec. Cor.; dug pits 18 x 18 x 12 ins. E. and W. of stake, 5 $\frac{1}{2}$ ft. dist., raised mound of earth 1 $\frac{1}{2}$ ft. high, 3 $\frac{1}{2}$ ft. base over it and in E. pit drove stake, 2 ft. long, 2 ins. sq., 12 ins. in the ground marked 1/16 S. on N. face.	
80.50	Cor. to Secs. 25, 26, 35 & 36. Land; mostly level Soil; 1st rate. All cultivated	
	S. on random bet. Secs. 35 & 36 Var. 19 $\frac{3}{4}$ ° E.	
	Set temp. cor. at 20, 40 & 60 chs. and at	
80.70	Intersect S. Bdy. T., 70 lks. W. of cor. to Secs. 1, 2, 35 & 36, thence N. 30' W. on true line	
	Var. 21 $\frac{1}{4}$ ° E.	
1.00	Leave garden	
2.00	Wagon road, E. and W., ascend hill.	