

## Subdivisional Lines of T. 4 N., R. 34 E., W.M.

Chains		Feet
47.00	Wagon road, S.W.	
52.25	Set stone, 12 x 11 x 10 ins., 8 ins. in the ground for meander cor. to fractional Secs. 26, 35, marked W.R. M.C. on E. face, and dug pits, 3 ft. sq., 12 ins. in the ground, 8 lks. E. of stone and raised mound of earth 2 ft. high 4½ ft. base over it.	
53.50	Wild Horse Creek, 10 lks. wide	
56.00	Bend of same, S.W.	
79.35	Cor. to Secs. 26, 27, 34 & 35, Land; rolling Soil; 1st rate. No timber, all cultivated.	
S. on random bet. Secs. 34 & 35		
Var. 19 3/4° E.		
40.00	Set temp. ¼ Sec. Cor., and at	
80.79	Intersect S. Bdy. T., 55 lks. W. of Cor. to Secs. 2, 3, 34 & 35, thence N. 23' W. on true line	
39.50	Wagon Road, N.E.	
40.79	Set post 4 ft. long, 4 ins. sq., 24 ins. in the ground, for ¼ Sec. Cor., marked ¼ S. on W. face, dug pits, 18 x 18 x 12 ins. N. and S. of post, 5½ ft. dist., raised mound of earth, 1½ ft. high, 3½ ft. base around it.	
42.00	O.R. and N. R.R., N.E. and S.W.	
49.00	Fence and field, E. and W.	
61.50	Wild Horse Creek, 10 lks. Wide, runs S.W.	
62.29	Set post, 4 ft. long, 4 ins. sq., 24 ins. in the ground for Meander Cor. to Secs. fractional 34 & 35, marked: W.R.M.C. with T. 4 N. on S., R. 34 E. & 35 on E. and S. 34 on W. faces and dug a pit, 3 ft. sq., 1 ft. deep, 8 lks. S. of Cor. and raised mound of earth, 2 ft. high, 4½ ft. base, around it.	
72.50	Wire fence, E. & W.	
80.00	Fence, E. and W.	
80.79	Cor to Secs. 26, 27, 34 & 35	