

Exterior Bdy. of T. 5 N., R. 35 E., W.M. (N. Bdy.)

Chains		Feet
	Land; broken Good grass Soil; good 2nd rate.	
<hr/> <p>Exterior Bdy. of T. 4 N., R. 35 E., W.M. (E. Bdy.) As surveyed by Wm. H. Odell, U.S. Deputy Surveyor Under Contract No. 114. Dated July 2nd, 1866.</p> <hr/>		
	N. on E. Bdy. of Sec. 36	
40.00	Set post Cor. for $\frac{1}{4}$ Sec.; drove charred stake, dug pits and raised mound as per instructions.	
80.00	Set post Cor. for Secs. 25, 36, 30 & 31, on side hill facing the E.; drove charred stake, dug pits and raised mound as per instructions.	
	This line passes along the side of ravine, course S. Grass good Soil; 2nd rate. Some pine timber in the ravine a short distance to the E.	
<hr/>		
	N. on E. Bdy. of Sec. 25	
	Var. 20°30' E.	
40.00	Set post Cor. for $\frac{1}{4}$ Sec. on level on summit of divide, bet. Pine Creek and Dry Creek, drove charred stake, dug pits and raised mound as per instructions.	
80.00	Set post Cor. for Secs. 24, 25, 19 & 30, on land aloping to N.E.; drove charred stake, dug pits and raised mound as per instructions.	
	Land; broken Grass good Soil; 2nd rate.	
<hr/>		
	N. on E. Bdy. of Sec. 24	
	Var. 21° E.	
40.00	Set post Cor. for $\frac{1}{4}$ Sec. on hill side facing the N.E.; dug pits and raised mound as per instructions.	
48.10	Small branch, 8 lks. N. course N.W.	