

Subdivisional Lines of T. 4 N., R. 35 E., W.M.

Chains		Feet
39.93	Set post Cor. for $\frac{1}{4}$ Sec.; drove charred stake, dug pits and raised mound as per instructions.	
79.87	To post Cor. Land; broken, good grass Soil; good 2nd rate.	
<hr/> N. bet. Secs. 2 & 3		
40.00	Set post Cor. for $\frac{1}{4}$ Sec. on level; drove charred stake, dug pits and raised mound as per instructions.	
64.35	Intersected 1st Standard Parallel N. 8.65 lks. W. of Standard Cor. for Secs. 34 & 35. At point of intersection, set Closing Cor. for Secs. 2 & 3; drove charred stake, dug pits and raised mound as per instructions. Land; broken, good grass Soil; 2nd rate.	
August 21, 1866.		
<hr/> N. bet. Secs. 33 & 34		
5.25	Ditch, fence, course E.&W.	
22.50	House brs. W., 40 lks.	
26.25	Leave field	
40.00	Set post Cor. for $\frac{1}{4}$ Sec.; drove charred stake, dug pits and raised mound as per instructions.	
60.55	Boise City and Walla Walla Stage Road, course N.E. & S.W.	
80.00	Set post Cor. for Secs. 27, 28, 33 & 34 on level; drove charred stake, and raised mound as per instructions. Land; rolling, good grass. Soil; good 2nd rate.	
<hr/> E. on random bet. Secs. 27 & 34		
Var. 20°30' E.		
40.00	Set post Cor. for $\frac{1}{4}$ Sec. temp.	
80.15	Intersected N. & S. line, 12 lks. N. of post N. 89° 55' W. on true line	
40.07	Set $\frac{1}{4}$ Sec. post Cor.; drove charred stake, dug pits and raised mound as per instructions.	