

## Subdivisional Lines of T 4 N R 35 E., W.M.

Chains		Feet
	and raised mound, as per instructions.	
80.00	Set post Cor. for Secs. 15, 16, 21 & 22; drove charred stake, dug pits and raised mound as per instructions. Land; broken, good grass Soil; 2nd rate.	
<hr/>		
	E. on random bet. Secs. 15 & 22	
		Var. 21° E.
40.00	Set temp. $\frac{1}{4}$ Sec. Cor.	
80.17	Intersected N. & S. line, 37 (lks.) S. of post Cor. S. 89° 44' W. on true line	
9.00	Boise City and Walla Walla Stage Road, course N.	
12.00	Enter field, course of fence, N. & S.	
40.08	Set post Cor. for $\frac{1}{4}$ Sec.; drove charred stake, dug pits and raised mound as per instructions.	
42.50	Pine Creek, course N.	
60.50	Leave field	
80.17	To post Cor. Land; rolling, good grass Soil; good 2nd rate.	
<hr/>		
	N. Bet. Secs. 15 & 16	
8.00	Road, course W.	
40.00	Set post Cor. for $\frac{1}{4}$ Sec.; drove charred stake, dug pits and raised mound as per instructions.	
80.00	Set post Cor. for Secs. 9, 10, 15 & 16; drove charred stake, dug pits and raised mound as per instructions. Land; rolling, good grass Soil; good 2nd rate.	
<hr/>		
	E. on random bet. Secs. 10 & 15	
		Var. 20° E.
40.00	Set temp. $\frac{1}{4}$ Sec. Cor.	
79.65	Intersected N. and S. line, 43 lks. N. of post Cor. N. 89° 42' W. on true line	
39.82	Set post Cor. for $\frac{1}{4}$ Sec. on level, drove charred stake, dug	