

Subdivisional Lines of T. 4 N R 35 E., W.M.

Chains		Feet
40.00	Set post Cor. for $\frac{1}{4}$ Sec., in small ravine, course S.W. drove charred stake, dug pits and raised mound as per instructions.	
65.49	Intersected 1st Standard Parallel, 7.98 lks. W. of post Cor. for Secs. 32, 33, T. 5 N., R. 35 E.; st point of intersec-tion set Closing Cor. for Secs. 4 & 5, drove charred stake, dug pits and raised mound as per instructions. Land; broken, good grass Soil; 2nd rate.	
N. bet. Secs. 31 & 32		
40.00	Set post Cor. for $\frac{1}{4}$ Sec.; drove charred stake, dug pits and raised mound as per instructions.	
80.00	Set post Cor. for Secs. 29, 30, 31 & 32; drove charred stake, dug pits and raised mound as per instructions. Land; rolling, good grass Soil; good 2nd rate.	
E. on random bet. Secs. 29 & 32		
Var. 20° 30' E.		
40.00	Set temp. $\frac{1}{4}$ Sec. post Cor.	
79.78	Intersected N. & S. line, 15 lks. N. of post Cor. N. 89° 54' W. on true line	
29.25	Wild Horse Creek, 4 lks. wide, course N.W.	
39.89	Set post Cor. for $\frac{1}{4}$ Sec.; drove charred stake, dug pits and raised mound as per instructions.	
79.78	To post Cor. Land; broken, good grass Soil; good 2nd rate.	
W. on random bet. Secs. 30 & 31		
40.00	Set temp. $\frac{1}{4}$ Sec. Cor.	
77.15	Intersected N. & S. line, 24 lks. N. of post Cor. N. 89°50' E. on true line	