

Subdivisional Lines of T. 4 N., R. 35 E., W.M.

Chains		Feet
	N. bet. Secs. 17 & 18	
40.00	Set post Cor. for $\frac{1}{4}$ Sec.; drove charred stake, dug pits and raised mound as per instructions.	
80.00	Set post Cor. for Secs. 7, 8, 17 & 18; drove charred stake, dug pits and raised mound as per instructions.	
	Land; gently rolling	
	Soil; 2nd rate.	
<hr/>		
	E. on random bet. Secs. 8 & 17	
		Var. 20°30' E.
40.00	Set temp. $\frac{1}{4}$ Sec. Cor.	
79.83	Intersected N. & S. line, 61 lks. S. of post Cor.	
	S. 89° 34' W. on true line	
39.91	Set post Cor. for $\frac{1}{4}$ Secs.; drove charred stake, dug pits and raised mound as per instructions.	
79.83	To post Cor.	
	Land; gently rolling, good grass	
	Soil; 2nd rate.	
<hr/>		
	W. bet. Secs. 7 & 18	
	On random	
40.00	Set temp. $\frac{1}{4}$ Sec.	
77.28	Intersected N. & S. line, 32 lks. N. of post Cor.	
	N. 89° 46' E. on true line	
37.28	Set $\frac{1}{4}$ Sec. Cor. post; drove charred stake, dug pits and raised mound as per instructions.	
77.28	To post Cor.	
	Land; rolling	
	Soil; 2nd rate.	
<hr/>		
	N. bet. Secs. 7 & 8	
37.00	Enter field, course of fence, E. & W.	
40.00	Set post Cor. for $\frac{1}{4}$ Sec; drove charred stake, dug pits and raised mound as per instructions.	
52.00	House faces E. about 150 lks.	
54.00	Leave field and cross small Spring branch, course N 5° W.	