

Resurvey of Subdivisional Lines of T. 4 N., R. 35 E., W.M.

Chains		Feet
78.00	To Cor. Land; rolling Soil; good Good grass	
<hr/>		
N. bet. Secs. 29 & 30		
40.00	Set post and made mound of earth for $\frac{1}{4}$ Sec. Cor.	
50.00	To Wild Horse Creek, the Bdy. to Reservation Land; rolling Soil; good Good Grass.	
<hr/>		
E. bet. Secs. 19 & 30		
40.00	Set post and made earth mound for $\frac{1}{4}$ Sec. Cor.	
60.00	Wild Horse Creek, Bdy. of Reservation Land; rolling Soil; good Good grass	
Oct. 24, 1871		
<hr/>		
Resurvey of Subdivisional Lines of T. 4 N., R. 35 E., W.M. As surveyed by Jas. P. Currin & Jas. E. Noland, U.S. Dep. Under their Special Contract Dated May 4th, 1887		Survs.
<hr/>		
Survey commenced May 17th, 1887, with Butts improved Solar Compass.		
Commencing at Cor. to Secs. 19, 20, 29 & 30, which is a old mound with pit in E. Sec., $5\frac{1}{2}$ ft. dist. the stake or post having disappeared I run		
W. on random bet. Secs. 19 & 30		
Var. 20° E.		
40.00	Set temp. $\frac{1}{4}$ Sec. Cor. and at	
75.60	Intersect W. Bdy. T, 36 lks. S. of Cor. to Secs. 19, 30, 24 & 25; thence S. $89^{\circ} 44'$ E. on true line	
Var. same		
15.00	Lane, N. & S., 30 ft. wide	