

Resurvey of Subdivisional Lines of T. 4 N R 35 E., W.M.

| Chains |  | Feet |
|--------|--|------|
|        | <p>T 4 N S 29 on N.E.<br/>                     R 34 E S 32 on S.E.<br/>                     S 31 on S.W. and S 30 on N.E. faces,<br/>                     with 1 notch on S. &amp; 5 notches on E. edges,<br/>                     dug pits, 18 x 18 x 12 ins. in each Sec., 5½ ft. dist.<br/>                     and raised mound of earth, 2 ft. high, 4½ ft. base around<br/>                     it.</p> <p>Land; rolling<br/>                     Soil; 1st rate.<br/>                     Mostly cultivated</p>                       |      |
|        | <p>E. on random bet. Secs. 29 &amp; 32<br/>                     Var. 20° E.<br/>                     Set temp. Cors., at 20, 40, 60 chs. and at<br/>                     30.68 Intersect E. Bdy., 65 lks. S. of Cor. to Secs. 28, 29, 32<br/>                     &amp; 33, thence<br/>                     S. 89° 32' W. on true line<br/>                     Var. 21° E.</p>  |      |
| 29.10  | <p>A willow, 6 ins. diam on E. bank of Wild Horse Creek, which<br/>                     I mark; U.R.M.C. with T 4 N on E. face, R 35 E., S 29<br/>                     on N. and S 32 on S. faces, for Meander Cor. to fractional<br/>                     Secs. 29 &amp; 32, from which<br/>                     A Balm, 16 ins. diam. brs. N. 5° E., 20 lks, dist.<br/>                     marked U.R.M.C.B.T.S. 29,<br/>                     No other trees in limits, and raised mound of stone<br/>                     alongside.</p> |      |
| 40.34  | <p>Set post, 3 ft. long, 3 ins. sq., 24 ins. in the ground<br/>                     for ¼ Sec. Cor., marked ¼ S. on N. face, dug pits, 18 x<br/>                     18 x 12 ins. E. &amp; W. of post, 5½ ft. dist. and raised<br/>                     mound of earth, 1½ ft. high, 3½ ft. base around it</p>   |      |
| 60.51  | <p>Deposited charred stake, 12 ins. in the ground for 1/16<br/>                     Sec. Cor., dug pits, 18 x 18 x 12 ins. E. &amp; W. of stake,<br/>                     5½ ft. dist., raised mound of earth, 1½ ft. high, 3½ ft.<br/>                     base over it and in E. pit, drove stake, 2 ft. long, 2<br/>                     ins. sq., 12 ins. in the ground, marked 1/16 S. on N.<br/>                     face.</p>   |      |