

Sub-subdivisions of T 4 N., R 35 E., W.M. (Sec. 31)

Chains		Feet
	S. 89° 49' E. on true line	
16.00	Deposited charred stake, 12 ins. in the ground for 1/16 Sec. Cor., dug pits 18 x 18 x 12 ins. E. & W. of stake, 5½ ft. dist., raised mound of earth, 1½ ft. high, 3½ ft. base over it and in E. pit; drove stake, 2 ft. long, 2 ins. sq., 12 ins. in the ground, marked: 1/16 S. on N. face.	
36.00	Deposited charred stake, 12 ins. in the ground for 1/16 Sec. Cor., dug pits 18 x 18 x 12 ins., E. & W. of stake, 5½ ft. dist., raised mound of earth, 1½ ft. high, 3½ ft. base over it and in E. pit; drove stake, 2 ft. long, 2 ins. sq., 12 ins. in the ground of marked: 1/16 S. on N. face.	
56.00	Deposited charred stake, 12 ins. in the ground for 1/16 Sec. Cor.; dug pits 18 x 18 x 12 ins. E. & W. of stake, 5½ ft. dist., raised mound of earth 1½ ft. high, 3½ ft. base over it and in E. pit; drove stake, 2 ft. long, 2 ins. sq., 12 ins. in the ground, marked: 1/16 S. on N. face.	
76.00	To point of beginning Land; mostly level Soil; 1st rate. Partly cultivated.	
	W. on random through center of Sec. 31 Var. 20° E. Commencing at ¼ Sec. Cor. bet. Secs. 31 & 32, set temp. Cors. at 20, 40, & 60 Chs., and at	
75.90	Intersect E. Bdy, 32 lks. S. of ¼ Sec. Cor., thence S. 89° 46' E. on true line	
15.00	Fence, N. & S.	
15.90	Deposited charred stake, 12 ins. in the ground for 1/16 Sec. Cor.; dug pits, 18 x 18 x 12 ins. E. & W. of stake, 5½ ft. dist.; raised mound of earth, ½ ft. high, 3½ ft. base over it and in E. pit; drove stake, 2 ft. long 2 ins. sq., 12 ins. in the ground, marked: 1/16 S. on N	