

Exterior Bdy. of T. 4 N., R. 36 E., W.M. (N. Bdy.)

Chains		Feet
75.00	To bottom of ravine	
80.00	<p>Set standard Cor. for Ts. 4 & 5 N., R. 36 E., on steep hill side. Cottonwood tree, 10 ins. in diam. 37 lks. due E. of Cor., marked B.T.; drove charred stake, dug pits and raised mound as per instructions.</p> <p>Land; very broken</p> <p>Grass good</p> <p>Soil; 1st rate.</p>	
<hr/> <p>Exterior Bdy. of T. 4 N., R. 36 E., W.M. (E. Bdy.) As surveyed by Wm. H. Odell, U.S. Deputy Surveyor. Under Contract No. 114, Dated July 2, 1866.</p> <hr/>		
<p>E. Bdy. of T 4 R 36 E., W.M.</p>		
<p>N. on E. Bdy. of Sec. 36</p>		
<p>Var. 19° 30' E.</p>		
11.25	Pine Creek, course W.	
40.00	<p>Set post Cor. for $\frac{1}{4}$ Sec., from which</p> <p>A Pine, 8 ins. diam. brs. N. 45° E. 93 lks.</p> <p>A Fir, 24 ins. diam. brs. N. 4° W., 61 lks.</p>	
30.00	<p>Set post Cor. for Secs. 25, 36, 30 & 31, from which</p> <p>A Fir, 20 ins. diam. brs. S. 25° W., 20 lks.</p> <p>A Larch, 24 ins. diam. brs. S. 45° E., 19 lks.</p> <p>A Pine, 30 ins. diam. brs. N. 50° E., 70 lks.</p> <p>A Fir, 12 ins. diam. brs. N. 45° W., 32 lks.</p>	
<p>This line passes through timber, larch, fir and pine,</p>		
<p>Under; the same with willow.</p>		
<p>Land; gently rolling</p>		
<p>Soil; 2nd rate.</p>		
<hr/> <p>N. on E. Bdy. of Sec. 25</p>		
<p>Var. 20° E.</p>		
40.00	<p>Set post Cor. for $\frac{1}{4}$ Sec. on side hill in thick underbrush, from which</p> <p>A larch, 4 ins. diam. brs. S. 20° E., 12 lks.</p> <p>A larch, 5 ins. diam. brs. N. 15° W., 15 lks.</p>	
43.75	Bottom of ravine, course N.W.	