

Subdivisional Lines of T. 4 N., R. 36 E., W.M.

Chains		Feet
	N. bet. Secs. 13 & 14	
39.00	Bottom of ravine, course W.	
40.00	Set post Cor. for $\frac{1}{4}$ Sec. from which	
	A fir, 18 ins. diam. brs. N. 43° E., 38 lks.	
	A fir, 12 ins. diam. brs. S. 5° W., 32 lks.	
71.30	Road, course W.	
80.00	Set post Cor. for Secs. 11, 12, 13 & 14; drove charred stake, and raised stone mound as per instructions.	
	Land; broken and stony	
	Good grass.	
<hr/>		
	E. on random bet. Secs. 12 & 13	
		Var. 21° E.
40.00	Set temp. $\frac{1}{4}$ Sec. Cor.	
80.20	Intersected N. and S. line, 49 lks. S. of post Cor.	
	S. 89° 39' W. on true line	
40.10	Set basalt stone, 5 x 9 x 14, Cor. for $\frac{1}{4}$ Sec.	
80.20	To post Cor.	
	Land; rolling and stony	
	Good grass.	
<hr/>		
	N. bet. Secs. 11 & 12	
40.00	Set post Cor. for $\frac{1}{4}$ Sec. on hillside, facing the W.; drove charred stake, and raised stone mound as per instructions	
80.00	Set post Cor. for Secs. 1, 2, 11 & 12; drove charred stake, and raised stone mound as per instructions.	
	Land; broken, good grass	
	Soil; 2nd rate.	
<hr/>		
	E. on random bet. Secs. 1 & 12	
		Var. 20° E.
40.00	Set temp. $\frac{1}{4}$ Sec. Cor.	
80.26	Intersected N. and S. line, 57 lks. S. of post Cor.	
	S. 89° 36' W. on true line	
40.13	Set basalt stone, 7 x 6 x 16 for $\frac{1}{4}$ Sec. Cor.	