

Subdivisional Lines of T. 4 N., R. 36 E., W.M.

Chains		Feet
80.26	To post Cor. Land; very broken, good grass.	
N. bet. Secs. 1 & 2		
35.25	Creek channel dry, course W.	
40.00	Made stone Cor. for $\frac{1}{4}$ Sec. on steep hillside, facing the S.; set basalt stone, 6 x 12 x 18.	
68.44	Intersected 1st Standard N. 12.87 W. of Standard Cor. for Secs. 35 & 36, T 5 N R 36 E.	
	Set Closing Cor.; drove charred stake, and raised stone mound as per instructions.	
	Land; very broken	
	Grass good	
	Soil; stony	
Sept. 27, 1866.		
N. bet. Secs. 34 & 35		
40.00	Set post Cor. for $\frac{1}{4}$ Sec. from which A Pine, 36 ins. diam. brs. S. 60° W., 26 lks. A Pine, 10 ins. diam. brs. N. 62° E., 18 lks.	
55.00	Pine creek channel dry course, W.	
80.00	Set post Cor. for Secs. 26 & 27, 34 & 35, from which A Pine, 24 ins. diam. brs. S. 25° E., 97 lks. A Pine, 30 ins. diam. brs. S. 45° W., 47 lks. A Pine, 20 ins. diam. brs. N. 30° W., 89lks. A Pine, 24 ins. diam. brs. N. 40° E., 79 lks.	
	Land; on S. side of Pine Creek, heavily timbered, Pine, Larch and Fir, on N. side, open, good grass.	
	Soil; stony.	
E. on random bet. Secs. 26 & 35		
Var. 20° 30' E.		
40.00	Set temp. $\frac{1}{4}$ Sec. Cor.	
80.25	Intersected N. and S. line, 15 lks. N. of Post Cor. N. 89° 54' W. on true line	
40.12	Set post Cor. for $\frac{1}{4}$ Sec. from which	