

Subdivisional Lines of T. 4 N., R. 36 E., W.M.

Chains		Feet
	<p>stake, dug pits and raised mound as per instructions.</p> <p>Land; broken</p> <p>Good grass</p> <p>Soil; 2nd rate.</p> <p style="text-align: right;">Oct. 7th, 1866.</p>	
	<hr/>	
	N. bet. Secs. 31 & 32	
17.00	Pine Creek, course W.	
40.00	Set basalt stone, 5 x 9 x 15, cor. for $\frac{1}{4}$ Sec.	
80.00	Set post Cor. for Secs. 29, 30, 31 & 32, in prairie; drove charred stake, dug pits and raised mound as per instructions.	
	Land; broken, good grass	
	Soil; 2nd rate.	
	<hr/>	
	E. on random bet. Secs. 29 & 32	
		Var. 20° 30' E.
40.00	Set temp. $\frac{1}{4}$ Sec. Cor.	
79.58	Intersected N. and S. line at post Cor.	
	W. on true line	
39.79	Set post Cor. for $\frac{1}{4}$ Sec.; drove charred stake, and raised mound as per instructions.	
79.58	To post Cor.	
	Land; broken, good grass	
	Soil; 2nd rate.	
	<hr/>	
	W. on random bet. Secs. 30 & 31	
40.00	Set temp. $\frac{1}{4}$ Sec. Cor.	
77.05	Intersected N. and S. line, 58 lks. S. of post Cor.	
	S. 89° 35' E. on true line	
37.05	Set post Cor. for $\frac{1}{4}$ Sec., from which	
	A Pine, 6 ins. diam. brs. N. 50° E., 26 lks.	
	A Pine, 8 ins. diam. brs. S. 70° W., 18 lks.	
77.05	To post Cor.	
	Land; broken, good grass	
	Soil; 2nd rate.	