

## Subdivisional Lines of T. 4 N., R 36 E., W.M.

Chains		Feet
	E. on random bet. Secs. 5 & 8	
		Var. 19° 30' E.
40.00	Set temp. $\frac{1}{4}$ Sec. Cor.	
80.08	Intersected N. and S. line, 54 lks. S. of post Cor.	
	S. 89° 37' W. on true line	
40.04	Set post Cor. for $\frac{1}{4}$ Sec.; drove charred stake, dug pits and raised mound as per instructions.	
80.05	To post Cor.	
	Land; broken, good grass	
	Soil; 2nd rate.	
<hr/>		
	W. on random bet. Secs. 6 & 7	
40.00	Set temp. $\frac{1}{4}$ Sec. Cor.	
76.80	Intersected N. and S. line, 36 lks. S. of post Cor.	
	S. 89° 23' E. on true line	
16.80	Road, course N.W.	
36.80	Set post Cor. for $\frac{1}{4}$ Sec. Cor.; drove charred stake, dug pits and raised mound as per instructions.	
76.80	To post Cor.	
	Land; broken, good grass	
	Soil; 2nd rate.	
<hr/>		
	N. bet. Secs. 5 & 6	
26.00	Enter field, course of fence, N.W.	
40.00	Set post Cor. for $\frac{1}{4}$ Sec.; drove charred stake, dug pits and raised mound as per instructions.	
57.75	Creek, 6 lks. wide, course W.	
64.00	Leave field	
68.41	Intersected 1st standard parallel, 1271 lks. W. of post Cor. for Secs. 31 and 32, T 5 N R 36 E.	
	Set closing Cor. for Secs. 5 & 6; deposited marked stone and made stone mound as per instructions.	
	Land; broken, good grass	
	Soil; good 2nd rate.	