

## Exterior Bdy. of T 4 N R 37 E., W.M. (N. Bdy.)

Chains		Feet
	This line passes over high rocky ridges. Some grass.	
	E. on S. Bdy. of Sec. 34, T 5 N R 37 E Var. 20° E.	
13.50	Crossed branch, 5 lks. wide, course N.W.	
40.00	Set post Standard Cor. for $\frac{1}{4}$ Sec. on hillside, facing to S.; drove charred stake, made stone mound as per instructions.	
62.00	Fir tree, 30 Ins. in diam.	
70.00	Enter timber.	
80.00	Set Standard Cor. for Secs. 34 & 35, from which A Larch, 14 ins. diam. brs. N. 50° W., 70 lks. dist. A " 24 " " " N. 70° E., 100 lks. dist. A Fir, 24 " " " S. 44° E., 30 lks. dist.	
	This line passes over gradually rising ground. Grass good Soil; 2nd rate. Timber; fir, larch, & pine.	
	E. on S. Bdy. of Sec. 35, T 5 N R 37 E Var. 20° E.	
40.00	Set post Standard Cor. for $\frac{1}{4}$ Sec., from which A fir tree, 10 ins. diam. N 37° E., 17 lks. A " " 8 " " S 47 $\frac{1}{2}$ ° W., 31 lks.	
80.00	Set standard Cor. for Secs. 35 & 36 on Fir tree, 24 ins. diam., from which A fir tree, 10 ins. diam. N. 51° W. links A fir tree, 10 ins. diam. N. 47° E., 18 lks. A fir tree, 10 ins. diam. S. 47° E 16 "	
	This line passes through thick timber, fir, pine and larch. Undergrowth same, and vinemaple.	
	E. on S. Bdy. of Sec. 36, T 5 N R 37 E Var. 20° E	
40.00	Set post Standard Cor. for $\frac{1}{4}$ Sec., from which A fir tree, 20 ins. in diam. brs. N. 74° W., 18 lks.	