

Exterior Bdy. of T 4 N R 37 E., W.M. (E. Bdy.)

Chains		Feet
	<p>A fir, 5 ins. diam. brs. N. 60° W., 46 lks. dist.</p> <p>Land; surface, mountainous</p> <p>Soil; 2nd & 3rd rate & worthless.</p> <p>Heavy timber, fir, tamarack and pine.</p>	
	<hr/> <p>N. on the E. Bdy. of Sec. 24</p> <p style="text-align: right;">Var. 14° 00' E.</p>	
1.00	Spring branch, course W.	
33.50	" " " N.W.	
40.00	Set basalt stone, 20 x 12 x 5 on S.W. face of spur for $\frac{1}{4}$ Sec. Cor.	
	A point of rocks, 10 ft. high, brs. N. 30° E. 16 lks. dist.	
49.50	Spring branch, course N.W.	
68.00	" " " N.W.	
80.00	Set basalt stone, 12 x 10 x 5 and drove stake on S.W. face of mountain for Cor. to Secs. 13, 24, 18 & 19; raised mounds of stone around stone and stake in lieu of pits.	
	<p>Land; surface mountainous</p> <p>Soil; 3rd rate and worthless.</p> <p>Some good timber on N. slopes, fir and tamarack.</p>	
	<hr/> <p>N. on the E. Bdy. of Sec. 13</p> <p style="text-align: right;">Var. 21° 00' E.</p>	
20.25	Spring branch, course N.W.	
40.00	Set fir post on N.W. face of spur for $\frac{1}{4}$ Sec. Cor.	
	A fir, 8 ins. diam. brs. N. 15° E., 191 lks. dist.	
	A pine, 7 ins. diam. brs. N. 18° W., 224 lks. dist.	
80.00	Set basalt stone, 16 x 10 x 4 on W. side of spur in mound of stone for Cor. to Sec. 12, 13, 7 & 18.	
	A fir, 16 ins. diam. brs. N. 33° E., 138 lks. dist.	
	No other tree	
	<p>Land; surface mountainous.</p> <p>Soil; 3rd rate and rocky.</p> <p>Some scattering fir, pine and tamarack timber.</p>	