

Exterior Bdy. of T 4 N R 37 E., W.M. (E. Bdy.)

Chains		Feet
	N. on the E. Bdy. of Sec. 12	Var. 19°45'E.
21.00	River bottom and timber, E. & W.	
29.00	Walla Walla River, 60 lks. wide, course W.	
40.00	Set basalt stone, 17 x 10 x 4 on S. side of mountain for $\frac{1}{4}$ Sec. Cor. A Pine, 40 ins. diam. brs. S. 76° E., 295 lks. dist. No other trees.	
66.00	Deep gulch opens S.E.	
80.00	Set basalt stone, 20 x 10 x 5 and drove stake on S.W. face of spur for Cor. to Secs. 1, 12, 6 & 7; raised mounds of stone and stake in lieu of pits. Land; surface mountainous Soil; 3rd rate and stony. Good timber in river bottom, fir, pine and tamarack & balm. May 30, 1879.	
	N. on the E. Bdy. of Sec. 1	Var. 22° 15' E.
	Up and across steep spur.	
40.00	Set basalt stone, 16 x 14 x 8 on rocky spur extending SE. for $\frac{1}{4}$ Sec. Cor. A fir, 16 ins. diam. brs. N. 46° W., 180 lks. dist. No other trees.	
59.50	Enter timber, course E. & W.	
75.30	Intersect 1st Standard Parallel N. 14.14 chs. W. of stand- ard Cor. to Tps. 5 N., Rs. 37 & 38 E. A Willow, 8 ins. diam. for C. Cor. to Tps. 4 N., Rs. 37 & 38 E., W.M. A Larch, 16 ins. diam. brs. S. 28° E., 27 lks. dist. A Fir, 6 ins. diam. brs. S. 47° W., 17 lks. dist. Land; surface, mountainous Soil; 3rd rate. Some good timber, fir, pine, tamarack and larch. May 31, 1879.	
	Resurvey of portion of the W. Bdy. of T. 4 N., R. 38 E., As surveyed by Robert F. Omeg, U.S. Deputy Surveyor. Under Contract No. 761, Dated June 16, 1905.	
	July 20, 1905: I begin at the cor. of secs. 19, 24, 25 & 30.	