

Subdivisional Lines of T 4 N., R. 37 E., W.M.

Chains		Feet
	Some value for grass, but principally for timber.	
	S. 89° 33' W. on a true line bet. Secs. 3 & 10 Var. 19° 00' E.	
22.00	Cross to N.W. side of spur.	
40.30	Set basalt stone, 18 x 12 x 4 on steep N.W. side of spur for $\frac{1}{4}$ Sec. Cor.	
51.00	A gulch, opens S.W.	
71.00	On spur, extending S.W.	
80.60	The Cor. to Secs. 3, 4, 9 & 10 Land; surface, broken and mountainous. Soil; 3rd rate. Some good grass, has some value for grazing. Aug. 22.	
	N. bet. Sec. 1 & 2 Var. 20° 00' E.	
40.00	Set pine post on level for $\frac{1}{4}$ Sec. Cor. A fir, 10 ins. diam. brs. E., 31 lks. dist. A fir, 10 ins. diam. brs. W., 33 lks. dist.	
76.30	Intersected 1st Standard Parallel N., 15.50 chs. W. of Cor. to Secs. 35 & 36 on standard line. Set fir post at intersection for Cor. to Sec. 1 & 2 A fir, 12 ins. diam. brs. S. 48° E., 22 lks. dist. A fir, 14 ins. diam. brs. S. 64° W., 45 lks. dist. Land; surface rolling, mountain plateau Soil; 3rd rate. Heavy good timber, tamarack, fir, spruce and pine. Yew, alder and Willow underbrush.	
	Cor. tree and witness tree were all standing as described in field notes, furnished by the office.	
	N. bet. Secs. 2 & 3 Var. 19° 00' E.	
8.50	On spur, course S.W.	