

Subdivisional Lines of T. 4 N., R. 37 E., W.M.

| Chains |   | Feet |
|--------|---|------|
| 43.00  | Enter dense undergrowth, brs. N.E. and S.W.               |      |
| 51.75  | Leave dense undergrowth, brs. E. and W.                   |      |
|        | Brink of precipitous descent into Walla Walla Canyon,     |      |
|        | inpassable ground. I offset as follows:                   |      |
|        | W. 6.00 chs., thence I run                                |      |
|        | N. 0° 02' W. on offset line for 7.00 Chs., thence E. 6.00 |      |
|        | Chs. to the true line.                                    |      |
|        | Through scattering timber and dense undergrowth.          |      |
| 73.75  | Foot of mountain, 1500 ft. below Sec. Cor.                |      |
|        | Left bank of Walla Walla River, 50 lks. wide, 3 ft. deep, |      |
|        | swift current, pure cold water, stony bottom, course      |      |
|        | S. 70° W.   |      |
|        | Over sandy bottom, not subject to inundation.             |      |
|        | Pack trail, course E. and W.                              |      |
|        | Ascend steep S. slope of mountain.                        |      |
| 80.00  | Set an ironstone, 15 x 12 x 8 ins., 10 ins. in the ground |      |
|        | struck rock, raised mound of stone around for Cor. of     |      |
|        | Secs. 10, 11, 14 and 15, marked with 4 notches on the     |      |
|        | S. and 2 notches on E. edges, from which                  |      |
|        | A fir, 36 ins. diam. brs. S. 38° W., 81 lks. dist.        |      |
|        | marked T. 4 N., R. 37 E., S. 15 B T                       |      |
|        | A fir, 20 ins. diam. brs. N. 20° W., 18 lks. dist.        |      |
|        | marked T 4 N., R. 37 E., S. 10 B T.                       |      |
|        | No other trees in limits. Mound and pits impracticable    |      |
|        | on account of steep slope.                                |      |
|        | Land; mountainous   |      |
|        | Soil; stony and gravelly, 4th and 3rd rate.               |      |
|        | Timber, tamarack, fir, pine and cottonwood.               |      |
|        | Undergrowth; mountain laurel, huckleberry, wild rose and  |      |
|        | buck brush. Mountainous land, 80.00 Chs.                  |      |
|        | E. on a random line bet. Secs. 11 & 14                    |      |
| 40.00  | Set temp. $\frac{1}{4}$ Sec. Cor.                         |      |
| 81.24  | Intersect N. and S. line, 61 lks. N. of the Cor. of Secs. |      |
|        | 11, 12, 13 and 14, established by me.                     |      |
|        | June, 1902  |      |
|        | Thence I run  |      |