

Dependent Resurvey of Part of W. Bdy. of T.4 N., R.38 E., W. M.

Chains

- 27.50 Fence, brs. E. and W.
 28.50 Highway, (Weston to Tollgate), brs. N.70°W. and S.70°E.
 28.90 Fence, brs. N.70°W. and S.70°E.
 31.00 House, brs. E., about 100 lks. dist.
 31.50 House, brs. E., about 200 lks. dist.
 32.00 House, brs. E., about 250 lks. dist.
 33.50 House, brs. E., about 200 lks. dist.
 33.50 House, brs. E., about 250 lks. dist.
 33.50 House, brs. W., about 50 lks. dist.
 33.80 House, brs. W., about 25 lks. dist.
 40.40 The $\frac{1}{4}$ Sec. Cor., which is a basalt stone, 14 x 12 x 8 ins., firmly set, marked $\frac{1}{4}$ on W. face.

At point for Cor.

Set an iron post, 3 ft. long, 1 in. diam., 16 ins. in the ground to bedrock, with the original stone deposited at the base, and in a mound of stone to top, for $\frac{1}{4}$ Sec. Cor., with brass cap marked

$\frac{1}{4}$
 S25 | S30
 1939

from which

A fir, 28 ins. diam., brs. N.19 $\frac{1}{2}$ °E., 38 lks. dist., marked $\frac{1}{4}$ S 30 B T. (Old B.T.)

A fir, 18 ins. diam., brs. N.45 $\frac{1}{2}$ °W., 39 lks. dist., marks grown over. (Old B.T.)

Thence

N.0°23'E., continuing measurements.

Desc. 496 ft. over N. slope.

- 54.30 Creek, 3 lks. wide, course W.; asc. 443 ft. over S. slope.
 66.45 Spur, slopes S.70°W.; desc. 408 ft. over N.W. slope.
 66.50 Leave heavy timber and dense undergrowth, brs. E. and W., enter scattering timber and undergrowth.
 80.24 The Cor. of Secs. 19, 24, 25 & 30, which is a dead and fallen fir tree, 14 ins. diam., with marks grown over.

At point for Cor.

Set an iron post, 3 ft. long, 2 ins. diam., 27 ins. in the ground, for Cor. of Secs. 19, 24, 25 & 30, with brass cap marked

T4N
 R37E | R38E
 S24 | S19
 S25 | S30