

Dependent Resurvey of Part of W. Bdy. of T 4 N R 38 E W M.

Chains

from which

- A dead fir, 14 ins. diam., brs. S.66°E., 22 lks. dist., marked T 4 N R 38 E S 30 B T. (Old B.T.)
- A fir stump, 12 ins. diam., brs. S.27°W., 17 lks. dist., marked B T. (Old B.T.)
- A fir stump, 14 ins. diam., brs. N.60°W., 46 lks. dist., marked T 4 N R 37 E S 24 B T. (Old B.T.)
- A fir, 6 ins. diam., brs. N.32½°E., 20 lks. dist., marked T 4 N R 38 E S 19 B T. (New B.T.)
- A fir, 6 ins. diam., brs. S.64½°E., 12 lks. dist., marked T 4 N R 38 E S 30 B.T. (New B.T.)
- A fir, 6 ins. diam., brs. S.38½°W., 20 lks. dist., marked T 4 N R 37 E S 25 B T. (New B.T.)
- A fir, 6 ins. diam., brs. N.59½°W., 44 lks. dist., marked T 4 N R 37 E S 24 B T. (New B. T.)

Land; mountainous.

Soil; rocky loam, 3rd rate.

Timber; fir, pine, spruce and tamarack.

Undergrowth: alder, willow, huckleberry, vinemaple, Oregon grape and fern.

N.0°33'E. bet. Secs. 19 & 24.

Desc. 55 ft. over NW. slope, through scattering timber and undergrowth.

- 1.00 Creek, 5 lks. wide, course W.; asc. 526 ft. over SW. slope.
- 18.90 Spur, slopes N.70°W.; desc. 553 ft. over N. slope.
- 33.40 Creek, 3 lks. wide, course N.80°W.; asc. 140 ft. over SW. slope.
- 40.12 The ¼ Sec. Cor., which is a basalt stone, 20 x 12 x 6 ins., firmly set in mound of stone, marked ¼ on W. face.

At point for Cor.

Set an iron post, 3 ft. long, 1 in. diam., 14 ins. in the ground to bedrock, with the original stone deposited at the base, and in a mound of stone to top, for ¼ Sec. Cor., with brass cap marked

↑
S24 | S19
1939

from which

A point of rock, 8 ft. high, brs. N.30°E., 16 lks. dist., marked X B 0. (Old B. 0.)

No bearing trees available.

Thence

N.0°09'E., continuing measurements.