

Dependent Resurvey of Part of W. Bdy. of T 4 N R 38 E W M.

Chains

Along W. slope.

- 40.30 Spur, slopes N.70°W.; desc. 290 ft. over N. slope.
 49.40 Creek, 1 lk. wide, course N.70°W.; asc. 103 ft. over SW. slope.
 56.30 Spur, slopes W.; desc. 339 ft. over NW. slope.
 66.20 Creek, 3 lks. wide, course W.; asc. 528 ft. over SW. slope.
 79.31 The Cor. of Secs. 13, 18, 19 and 24, which is a basalt stone, 14 x 12 x 6 ins., firmly set, marked with three grooves on N. and S. faces.

At point for Cor.

Set an iron post, 3 ft. long, 2 ins. diam., 27 ins. in the ground, with the original stone deposited at the base, for Cor. of Secs. 13, 18, 19 and 24, with brass cap marked.

T4N
 R37E | R38E
 S13 | S18
 S24 | S19
 1939

raise a mound of stone, 3 ft. base, 2 ft. high, W. of Cor.

No bearing trees available.

Land; mountainous.

Soil; rocky loam, 3rd rate.

Timber; fir, pine, spruce and tamarack.

Undergrowth; alder, willow, huckleberry and vinemaple.