

## Subdivisional Lines of T 4 N R 38 E., W.M.

Chains		Feet
	<p>marked <math>\frac{1}{4}</math> S B T</p> <p>A fir, 10 ins. diam. brs. N. 80° W., 193 lks. dist. marked <math>\frac{1}{4}</math> S B T</p>	
79.60	<p>The Cor. to Secs. 20, 21, 23 &amp; 29</p> <p>Land; rolling</p> <p>Densely covered with forests of pine, fir and tamarack, much being dead and fallen.</p> <p>Thick undergrowth; fir and buckbrush, 79.60 Chs.</p> <p>Soil; good 2nd rate.</p>	
	<p>N. bet. Secs. 20 &amp; 21</p> <p style="text-align: right;">Var. 20° E.</p>	
40.00	<p>Set a post, 3<math>\frac{1}{2}</math> ft. long, 3 ins. sq., with marked stone, 24 ins. in ground for <math>\frac{1}{4}</math> Sec. Cor., marked <math>\frac{1}{4}</math> S. on W. face, from which:</p> <p>A fir, 36 ins. diam. brs. N. 64° E., 38 lks. dist. marked <math>\frac{1}{4}</math> S B T</p> <p>A fir, 30 ins. diam. brs. N. 60° W., 30 lks. dist. marked <math>\frac{1}{4}</math> S B T</p>	
66.50	<p>To the S. edge of an impassable canyon and mark a fir, 11 ins. diam. W. C. T 4 N S 16 on N.E., R. 38 E., S. 21 on S.E., S. 20 on S.W. and S. 17 on N.W. faces, with 3 notches on S. and 4 notches on E. edges, from witness Cor. to Secs. 16, 17, 20 &amp; 21, from which</p> <p>A fir, 20 ins. diam. brs. N. 80° E., 16 lks. dist. marked T 4 N R 38 E S 16 W.C.B T.</p> <p>A fir, 18 ins. diam. brs. S. 60° E., 37 lks. dist. marked T 4 N R 38 E S 21 W. C. B T.</p> <p>A fir, 18 ins. diam. brs. S. 61° W., 54 lks. dist. marked T 4 N R 38 E S 20 W.C.B T.</p> <p>A fir, 20 ins. diam. brs. N. 20° W., 18 lks. dist. marked T. 4 N.R 38 E S 17 W C B T.</p> <p>Land; gently rolling</p> <p>Densely covered with forests of pine, fir and tamarack, 66.50 Chs.</p> <p>Undergrowth; fir and buckbrush</p> <p>Soil; good 2nd rate.</p>	
		Sept. 21st, 1883