

Subdivisional Lines of T 4 N R 38 E., W.M.

Chains		Feet
	<p>From the Cor. to Secs. 5, 6, 31 & 32, on the S. Bdy. of the tp. which is a post, 4 ins. sq., marked T 4 N S 32 on N E T 3 N R 38 E S 5 on S E S 6 on S W and S 31 on N W faces, from which:</p> <p>A tamarack, 8 ins. diam. brs. N. 42° E., 16 lks. dist. marked T 4 N R 38 E S 32 B T</p> <p>A pine, 10 ins. diam. brs. S. 80° E., 18 lks. dist. marked T 3 N R 38 E S 5 B T</p> <p>A pine, 10 ins. diam. brs. S. 56° W., 12 lks. dist. marked T 3 N R 38 E S 6 B T</p> <p>A tamarack, 10 ins. diam. brs. N. 70° W., 18 lks. dist. marked T 4 N R 38 E S 31 B T</p> <p>Thence I run,</p> <p>N. bet. Secs. 31 & 32</p> <p style="text-align: right;">Var. 21° 30' E.</p>	
40.00	<p>Set a post, 3½ ft. long, 3 ins. sq., with marked stone, 24 ins. in ground for ¼ Sec. Cor., marked ¼ S. on W. face, from which</p> <p>A fir, 15 ins. diam. brs. S. 10° E., 35 lks. dist. marked ¼ S.B.T.</p> <p>A fir, 15 ins. diam. brs. N. 45° W., 85 lks. dist. marked ¼ S.B.T.</p>	
72.50	Wagon road, course N.W. and S.E.	
80.00	<p>Set a post, 4½ ft. long, 4 ins. sq., with marked stone, 24 ins. in ground for Cor. to Secs. 29, 30, 31 & 32, marked T 4 N S 29 on N.E., R 38 E S 32 on S E S 31 on S W and S 30 on N W faces with 1 notch on S and 5 notches on E edges, from which:</p> <p>A fir, 10 ins. diam. brs. N. 60° E., 24 lks. dist. marked T 4 N R 38 E S 29 B T</p> <p>A fir, 12 ins. diam. brs. S. 78° E., 29 lks. dist. marked T 4 N R 38 E S 30 B T</p> <p>A fir, 6 ins. diam. brs. S. 71° W., 28 lks. dist. marked T 4 N R 38 E S 31 B T</p> <p>A fir, 10 ins. diam. brs. N. 42° W., 17 lks. dist. marked T 4 N R 38 E S 30 B T</p>	
	<p>Land; rolling</p> <p>Densely covered with forests of pine, fir and tamarack,</p> <p>80 Chs.</p> <p>Thick undergrowth, fir and buckbrush, 80 Chs.</p> <p>Soil; sandy loam, 2nd rate.</p>	