

Subdivisional Lines of T 4 N R 38 E W.M.

Chains		Feet
	<p>A fir, 12 ins. in diam. brs. S. 57° 30' E. 8 lks. dist., marked T 4 N R 38 E S 1 B T</p> <p>A fir, 10 ins. in diam. brs. S. 34° 30' W., 20 lks. dist., marked T 4 N R 38 E S 2 B T.</p> <p>Land; mountainous, Soil, 1st and 2nd rates, Timber, fir, pine, spruce; Undergrowth, willow, maple and wild berry. Mountainous or heavily timbered land or land covered with dense undergrowth and exceptionally difficult to survey. 80.00 Chs. July 21, 1905</p> <hr/> <p>Thence I run, E. on a random line bet. Secs. 12 & 13</p>	
40.00	Set temp $\frac{1}{4}$ Sec. Cor.	
81.20	Intersect the E. Bdy. of the T.50 lks. S. of the Cor. for Secs. 7, 12, 13 & 18, heretofore described, thence I run, S. 89° 39' W. on a true line bet. Secs. 12 & 13 Descend through heavy timber and dense undergrowth, over E. slope	
41.20	Set a fir post 3 ft. long, 3 ins. sq., 24 ins. in the ground for $\frac{1}{4}$ Sec. Cor., marked $\frac{1}{4}$ S. 12 on N. and 13 on S. face; from which A fir, 30 ins. diam. brs. S. 67° E., 28 lks. dist. marked $\frac{1}{4}$ S 13 B T A fir, 12 ins. diam. brs. N., 41° E., 32 lks. dist., marked $\frac{1}{4}$ S 12 B T	
43.25	A spring branch, 2 lks. wide, brs. S. Thence over almost level land through heavy timber and dense undergrowth.	
81.20	The Cor. of Secs. 11, 12, 13 & 14 Land; mountainous Soil, 1st and 2nd rates. Timber, fir, pine, spruce Undergrowth, willow, maple and wild berry Mountainous or heavily timbered land or land covered with dense undergrowth and exceptionally difficult to survey. 81.20 Chs.	
	<hr/> <p>From the Cor. of Secs. 1, 2, 11 & 12, I run N. 89° 39' E. on a random line bet Secs. 1 & 12</p>	
40.00	Set temp. $\frac{1}{4}$ Sec. Cor.	