

Dependent Resurvey of Part of S. Bdy. of T 4 N R 38 E.,

Chains	Feet
--------	------

A pine, 16 ins. diam., brs. S. 50° W., 13 lks. dist., marked $\frac{1}{4}$ S B T. Obliterated marks. (Old B.T.)

A spruce, 26 ins. diam., brs. N. 30° E., 30 lks. dist., marked $\frac{1}{4}$ S 32 B T (New B.T.)

A spruce, 16 ins. diam., brs. N. 18 $\frac{1}{2}$ ° W., 33 lks. dist., marked $\frac{1}{4}$ S 32 B T. (New B.T.)

Thence
N. 89° 40' W., continuing measurements.

Asc. 5 ft. over N.E. slope.

42.40 New position for the closing cor. of Secs. 5 & 6, hereinafter described.

Asc. 137 ft. over NE. slope.

43.85 Trail, brs. N. and S.

63.85 Spur, slopes N.; desc. 7 ft. over NW. slope.

67.10 Bottom of descent, bears N. and S.; asc. 38 ft. over NE. slope.

75.00 Top of ascent, bears N. and S.; over rolling land.

79.80 Dirt road, bears N. and S.

80.78 The Cor. of Secs. 31 & 32, which is a post, 30 ins. long, 4 ins. sq., firmly set, marked with 5 notches on E. and 1 notch on W. side.

At point for Cor;

Set an iron post, 3 ft. long, 2 ins. diam., 27 ins. in the ground, with the marked stake deposited at the base, for Cor. of secs. 31 and 32, with brass cap marked

T4NR38E
S31|S32
T3NR38E
B 6
1939

from which

A pine, 14 ins. diam., brs. S. 45° W., 12 lks. dist., marked R 38 E B T. Obliterate marks (Old B.T.)

A dead tamarack, 16 ins. diam., brs. N. 70° W., 18 lks. dist., marked T 4 N R 38 E S 31 B T. (Old B.T.)

A spruce, 20 ins. diam., brs. N. 4 $\frac{1}{2}$ ° E., 18 lks. dist., marked T 4 N R 38 E S 32 B T. (New B.T.)

A spruce, 18 ins. diam., brs. N. 49° W., 37 lks. dist., marked T 4 N R 38 E S 31 B T. (New B.T.)

Land; mountainous and rolling.

Soil; sandy loam; 2nd rate.

Timber, fir, pine, spruce, tamarack, and yew.

Undergrowth, alder, willow, huckleberry, and vinemaple.

Dependent Resurvey of Part of Subdivision of T. 4 N., R. 38 E.

"Reestablishment of the surveys of secs. 29, 30, 32, 33, and 34, executed by Frank W. Campbell, Deputy Surveyor, in