

Dependent Resurvey of Part of Subdivision of T 4 N., R. 38 E.

Chains		Feet
	marked T 4 N R 38 E S 26 B T (Old B.T.)	
	A fir, 24 ins. diam., brs. S. 11° E., 564 lks. dist., marked T 4 N R 38 E S 35 B T. (New B.T.)	
	A fir, 16 ins. diam., brs. S. 54° W., 204 lks. dist., marked T 4 N R 38 E S 34 B T. (New B.T.)	
	A fir, 12 ins. diam., brs. N. 47 $\frac{1}{2}$ ° W., 122 lks. dist., marked T 4 N R 38 E S 27 B T. (New B.T.)	
	Land; rolling and mountainous. Soil, sandy loam; 2nd and 3rd rate. Timber, fir, pine, spruce, and tamarack. Undergrowth, alder, willow, huckleberry, and buckbrush.	
	From the cor. of Secs. 33 & 34, on the S. bdy. of the Tp., heretofore described.	
	N. 0° 22' W., bet. Secs. 33 & 34.	
	Desc. 122 ft. over NE. slope, through heavy timber and dense undergrowth.	
4.75	Lookingglass Creek, 7 lks. wide, course S. 80° E.; asc. 399 ft. over S. slope, changing to SW. slope.	
29.50	Spur, slopes W.; desc. 68 ft. over NW. slope.	
40.25	Proportionate measurement.	
	Set an iron post, 3 ft. long, 1 in. diam., 27 ins. in the ground, for $\frac{1}{4}$ sec. cor., with brass cap marked	
	from which	
	A fir, 20 ins. diam., brs. N. 68° E., 31 lks. dist., marked $\frac{1}{4}$ S 34 B T.	
	A fir, 18 ins. diam. brs. N. 71 $\frac{1}{2}$ ° W., 31 lks. dist., marked $\frac{1}{4}$ S 33 B T.	
	Desc. 127 ft. over NW. slope, changing to N. slope.	
54.75	Enter swamp, brs. E. and W.	
60.00	Leave swamp, brs. E. and W.; asc. 27 ft. over S. slope.	
63.30	Skyline road, brs. E. and W.	
67.25	Top of ascent, brs. NW. and SE.; desc. 41 ft. over NE. slope.	
80.50	The cor. of secs. 27, 28, 33 & 34, which is a basalt stone, 20 x 15 x 4 ins., firmly set, marked with 3 notches on E. and 1 notch on S. edge.	
	At point for cor.	
	Set an iron post, 3 ft. long, 2 ins. diam., 27 ins. in the ground, with the original stone deposited at the base, for cor. of secs. 27, 28, 33, and 34, with brass cap marked	