


Dependent Resurvey of Part of Subdivisions of T 4 N R 38 E.

Chains		Feet
	Thence S. 89° 58' W., continuing measurements. Over rolling land.	
41.20	Enter, meadow, brs. N. and S.; leave heavy timber and dense undergrowth, brs. N. and S.	
45.20	Leave meadow, brs. N. and S., reenter heavy timber and dense undergrowth, brs. N. and S.; asc. 112 ft. over NE. slope.	
62.90	Spur, slopes N; desc. 113 ft. over NW. slope.	
79.90	Draw, course NW.; asc. 5 ft. over NE. slope.	
80.31	The cor. of secs. 27, 28, 33 & 34, heretofore described Land, mountainous Soil, sandy loam; 2nd and 3rd rate. Timber, fir, pine, spruce, and tamarack. Undergrowth, alder, willow, vinemaple, and huckleberry.	
	From the cor. of secs. 32 and 33, on the S. bdy. of the Tp., heretofore described. N. 0° 52' W., bet. Secs. 32 & 33. Asc. 32 ft. over SW. slope, through heavy timber and dense undergrowth.	
12.65	Round topped spur, slopes W.; desc. 126 ft. over NW. slope, changing to NE. slope.	
12.70	Old dirt road, brs. NW. and S.E.	
19.34	Same dirt road, brs. NE. and SW.	
29.00	Same dirt road; brs. NW. and SE.	
31.50	Highway, (Elgin to Tollgate), brs. N. 60° W. and S. 60° E.	
32.85	Lookingglass Creek, 2 lks. wide, course E.; asc. 40 ft. over SE. slope.	
38.00	Skyline road, brs. E. and W.	
40.01	The $\frac{1}{4}$ Sec. Cor., which has been perpetuated with a stone 9 x 8 x 6 ins., firmly set, with no visible marks. At point for Cor. Set an iron post, 3 ft. long, 1 in. diam.; 27 ins. in the ground, with the perpetuated stone deposited at the base, for $\frac{1}{4}$ Sec. Cor., with brass cap marked	
		
	from which	
	A dead pine, 24 ins. diam., brs. N. 82° E., 93 lks. dist., marked $\frac{1}{4}$ S B T (Old B.T.)	
	A pine, 24 ins. diam., brs. S, 68° W., 59 lks. dist., marks grown over. (Old B.T.)	