

Dependent Resurvey of Part of Subdivisions of T 4 N., R 38 E

Chains		Feet
	Store room for Forest Service, brs. S. 52° E., about 600 lks. dist.	
	Office of Forest Service, brs. S. 35° E., about 500 lks. dist.	
	New Forest Service house, brs. S. 23½° E., about 800 lks. dist.	
	Old Forest Service house, brs. S. 6° E., about 800 lks. dist.	
	Thence	
	N. 0° 08' E., continuing measurements.	
	Asc. 106 ft. over gradual SE. slope.	
43.66	Civilian Conservation Corps building, brs. S. 60½° E., about 3.00 chs. dist.	
48.50	Target Meadow Road, brs NE. and S.W.	
64.00	Top of ascent, brs. E. and W.; desc. 13 ft. over N. slope.	
80.07	Proportionate measurement.	
	Set an iron post: 3 ft. long, 2 ins. diam., 27 ins. in the ground, for cor. of secs. 28, 29, 32 & 33, with brass cap marked	
	T4NR38E S29 S28 S32 S33 1939	
	A fir, 10 ins. diam., brs. N. 44° E., 10 lks. dist., marked T 4 N R 38 E S 28 B T.	
	A fir, 10 ins. diam., brs. S. 61° E., 10 lks. dist., marked T 4 N R 38 E S 33 B T.	
	A fir, 11 ins. diam., brs. S. 70° W., 38 lks. dist., marked T 4 N R 38 E S 32 B T.	
	A fir, 13 ins. diam., brs. N. 78° W., 8 lks. dist., marked T 4 N R 38 E S 29 B T.	
	Land; rolling and mountainous. Soil; sandy loam; 2nd rate. Timber; fir, pine, spruce, and tamarack. Undergrowth, alder, willow, huckleberry, buckbrush and vinemaple	
	From the cor. of secs. 27, 28, 33 & 34, heretofore described.	
	S. 89° 44' W., bet. Secs. 28 & 33.	
	Asc. 47 ft. over gradual NE. slope, through heavy timber and dense undergrowth.	
32.00	Round topped spur, slopes N.; desc. 10 ft. over gradual NW. slope.	
36.00	Creek, 2 lks. wide, course N.; asc. 25 ft. over gradual NE. slope.	
40.53	The ¼ sec. Cor., determined by reference to the record bearings and distances to the original bearing trees.	