

Dependent Resurvey of Part of Subdivisions of T 4 N R 38 E.

Chains		Feet
69.95	Highway, (Weston to Tollgate), brs. E. and W.	
71.00	McIntyre Lookout Road, brs. NW. and SE.	
73.35	Fence, brs. E. and W.	
78.40	Small draw, course NE.; over rolling land.	
80.12	The cor. of secs. 29, 30, 31 & 32, determined by reference to the record bearings and distances to the original bearing trees.	
	At point for cor.	
	Set an iron post, 3 ft. long, 2 ins. diam., 27 ins. in the ground, for cor. of secs. 29, 30, 31 & 32, with brass cap marked	
	<p>T4NR38E S30 S29 S31 S32 1939</p>	
	from which	
	A dead fir, 24 ins. diam., brs. N. 60° E., 24 lks. dist., marks grown over. (Old B.T.)	
	A dead fir, 20 ins. diam., brs. S. 78° E., 29 lks. dist., marks grown over. (Old B.T.)	
	A fir, 14 ins. diam., brs. S. 71° W., 28 lks. dist., marks grown over. (Old B.T.)	
	A fir, 30 ins. diam., brs. N. 42° W., 17 lks. dist., marks grown over. (Old B.T.)	
	A fir, 14 ins. diam., brs. N. 82° E., 43 lks. dist., marked T 4 N R 38 E S 29 B T. (New B.T.)	
	A spruce, 20 ins. diam., brs. S. 68° E., 48 lks. dist., marked T 4 N R 38 E S 32 B T. (New B.T.)	
	Land; rolling, Soil; sandy loam; 2nd rate. Timber, fir, pine, spruce, and tamarack. Undergrowth, alder, huckleberry, willow, vinemaple, and Oregon grape.	
	From the cor. of secs. 28, 29, 32 & 33, heretofore described.	
	N. 89° 51' W., bet. Secs. 29 & 32.	
	Along gradual N. slope, through heavy timber and dense undergrowth.	
8.00	Desc. 57 ft. over gradual NW. slope.	
23.90	Spring branch, 1 lks. wide, course N.; asc. 68 ft. over gradual NE. slope.	
40.31	Proportionate measurement.	
	Set an iron post, 3 ft. long, 1 in. diam., 27 ins. in the ground, for $\frac{1}{4}$ Sec. Cor., with brass cap marked	
	<p>$\frac{1}{4}$ S 29 $\frac{1}{4}$ S 32 1939</p>	