

## Exterior Lines of T. 4 S., R. 30 E. W.M.

Chains		Feet	
	<p>Land; surface undulating, Soil; 3rd and 2nd rate; some scattering Pine timber, mostly open good grass.</p> <p style="text-align: right;">June 11, 1882.</p>		
	<p>General Description</p> <hr/> <p>This Tps. is nearly all a plateau, the larger part undulating and slightly rolling. There is one deep canyon in the N.W. part occupying nearly three Sections. The soil is larger part 3rd rate, about <math>\frac{1}{4}</math> 2nd rate and adaptable to farming. A small part 1st rate. About <math>\frac{1}{4}</math> is heavily timbered. <math>\frac{1}{4}</math> prairie, remainder open or scattering timber. Prairie and open timber produces excellent grass. There are two settlements in this Township.</p> <hr/> <p>Subdivisional Lines of Tps 4 S., R. 30 E. W.M. As surveyed by George S. Pershin, U.S. Deputy Surveyor, Under Contract No. 430, Dated March 23, 1882.</p> <hr/> <p>I begin at the Cor. to Sec. 35 and 36 on the S. Bdy. of T. 4 S., R. 30 E. which is a stone 18 x 12 x 6 ins. in mound of stone in open glade with mound of stone alongside and marked with 1 notch on E. and 5 notches on W. edges, A Pine 8 ins. diam. brs. N. 78° W. 226 lks. dist. Marked T. 4 S., R. 30 E., S. 35 B.T. No other trees. Sunday, commenced June 12th 1882, with a Burt's improved Solar Compass, thence I run, N. bet. Secs. 35 and 36. Var. 19° 30' E.</p>		
32.60	A Brook, 4 lks. wide, course S.E.		
40.00	Set a basalt stone 17 x 12 x 5 ins. 12 ins. in ground on slight S. slope in open glade for $\frac{1}{4}$ Sec. Cor., marked $\frac{1}{4}$ on W. face.		