

## Subdivisional Lines of T. 4 S., R. 30 E. W.M.

Chains		Feet
	Var. 19° 30' E.	
39.99	Set a basalt stone 12 x 10 x 8 ins. on slight S. slope in open glade in mound of stone for $\frac{1}{4}$ Sec. Cor., marked $\frac{1}{4}$ on N. face.	
79.98	The Cor. to Secs. 25, 26, 35 and 36. Land; surface undulating, Soil; 3rd and 2nd rate; open scattering Pine timber with open glades.	
	N. bet. Sec. 25 and 26,  Var. 19° 00' E.	
	Undulating,	
40.00	Set a basalt stone 18 x 12 x 8 ins. 12 ins. in ground on S. slope on N. side of small ravine for $\frac{1}{4}$ Sec. Cor., marked $\frac{1}{4}$ on W. face,  A Pine 24 ins. diam. brs. N. 57° E. 56 lks. dist. marked $\frac{1}{4}$ S. B.T.  No trees W., raised a mound of stone alongside.	
65.00	A brook 4 lks. wide, course S. E.	
80.00	Set a stone 16 x 8 x 7 ins. and post 4 ft. long 4 ins. square in mound of stone on S.W. slope for Cor. to Secs. 23, 24, 25 and 26. Stone marked with 2 notches on S. and 1 notch on E. edges. Post marked,  T 4 S., S 24 on N.E. R. 30 E., S. 25 on S.E. S. 26 on S.W. S. 23 on N.W.  Land; surface undulating, Soil; 2nd and 3rd rate, some Pine, Tamarack and Fir timber, but mostly open.	
	E. on a random line bet. Secs. 24 and 25,  Var. 20° 15' E.	
21.00	Wagon road, course N.W. and S.E.	
40.00	Set temp. $\frac{1}{4}$ Sec. Cor.	