

Subdivisional Lines of T. 4 S., R. 30 E.

| Chains | | Feet |
|----------------|---|------|
| 80.00 | <p>No trees, raised mound of stone alongside in lieu of pits.</p> <p>Set a basalt stone 15 x 8 x 7 ins., 10 ins. in ground on slight N.E. slope for Cor. to Secs. 22, 23, 26 and 27, marked with 2 notches on S. and E. edges from which,</p> <p style="padding-left: 40px;">A Pine 10 ins. diam. brs. S. 14° E. 34 lks. dist. marked T. 4 S., R. 30 E., S. 26 B.T.</p> <p style="padding-left: 40px;">A Pine 10 ins. diam. brs. S. 65° W. 98 lks. dist. marked T. 4 S., R. 30 E. S. 27 B.T.</p> <p>No other trees near, raised a mound of stone alongside in lieu of pits.</p> <p>Land; surface undulating,</p> <p>Soil; 3rd and 2nd rate; scattering Pine, Tamarack. Timber with open glades. Good grass.</p> | |
| 40.00 | <p>E. on a random line bet. Secs. 23 and 26,</p> <p style="text-align: right;">Var. 20° 00' E.</p> <p>Descending,</p> <p>Set temp. $\frac{1}{4}$ Sec. Cor.</p> | |
| 61.50 | <p>A brook 6 lks. wide, course S.E., descent 150 ft.</p> | -150 |
| 80.42 | <p>Intersected N. and S. line 52 lks. S. of Cor. to Secs. 23, 24, 25 and 26 from which Cor. I run,</p> <p>S. 89° 38' W. on a true line bet. Sec. 23 and 26.</p> <p style="text-align: right;">Var. 20° 15' E.</p> | |
| 40.21 | <p>Set a basalt stone 15 x 8 x 7 ins. 10 ins. in ground, on level in swale for $\frac{1}{4}$ Sec. Cor., marked $\frac{1}{4}$ on N. face.</p> <p style="padding-left: 40px;">A Pine 18 ins. diam. brs. N. 34° W. 21 lks. dist. marked $\frac{1}{4}$ S. B.T.</p> <p style="padding-left: 40px;">A Pine 16 ins. diam. brs. S. 44° W. 29 lks. dist. marked $\frac{1}{4}$ S. B.T.</p> | |
| 80.42 | <p>The Cor. to Secs. 22, 23, 26 and 27.</p> <p>Land; surface rolling,</p> <p>Soil; 3rd and 2nd rate, some thick grass and some scattering Pine, Tamarack and Fir. Timber and open glades. Good grass.</p> | |
| June 13, 1882. | | |