

Subdivisional Lines of T. 4 S., R. 30 E., W.M.

Chains		Feet
39.89	Set a basalt stone 14 x 12 x 4 ins. in mound of stone in large open glade, on E. slope for $\frac{1}{4}$ Sec. Cor., marked $\frac{1}{4}$ on N. face.	
79.78	The Cor. to Secs. 9, 10, 15 and 16. Land; surface rolling and sloping N. Soil; 3rd and 2nd rate, open timber Pine, Tamarack and Fir with open glades, good grass. <hr/> <i>June 15 1882</i>	
	N. bet. Sec. 9 and 10. Var. 21° 00' E.	
8.00	A brook 10 lks. wide, course N.E. Descent about 80 ft., Leave timber, course N.E. and S.W.	
40.00	Set a basalt stone 18 x 10 x 6 ins. on S. slope in mound of stone for $\frac{1}{4}$ Sec. Cor., marked $\frac{1}{4}$ on W. face.	
52.50	Top of knoll, about 200 ft. Above brook,	
80.00	Set a post 4 ft. long 4 ins. square in mound of stone on slight N. slope for Cor. to Secs. 3, 4, 9 and 10 marked, T. 4 S., S. 3 on N.E. R. 30 E., S. 10 S.E. S. 9 S.W. S. 4 N.W., with 5 notches on S. and 3 notches on E. side. Descent from knoll about 100 ft. Land; surface rolling, Soil; 3rd and 2nd rate, some Pine, timber on N. side of knoll and S. of Brook, remainder open. Good grass.	
	E. on a random line bet. Secs. 3 and 10. Var. 21° 10' E.	
40.00	Set temp. $\frac{1}{4}$ Sec. Cor.	
79.74	Intersected N. and S. line 20 lks. N. of Cor. to Secs.	