

1.
 Exterior Lines of T. 5 S., R. 31 E. W.M.
 As surveyed by George S. Pershin, U.S. Deputy Surveyor,
 Under Contract No. 373,
 Dated Sept. 17, 1880

| Chains | | Feet |
|--------|--|------|
| | <p>W. on a random line along the N. Bdys. of Secs. 1, 2, 3, 4, 5 and 6.</p> <p style="text-align: right;">Var. 19° 30' E</p> <p>I set temp. half-mile and mile posts at every 40 and 80 Chs. and at 5 miles 79 Chs. and 53 lks. to a point 76 lks. N. of the Cor. to Tps. 4 and 5 S., Rs. 30 & 31 E., making my corrections 13 lks. S. per mile and my course N. 89° 54' E.</p> <p>I therefore begin at the Cor. to Tps. 4 and 5 S., Rs. 30 and 31 E. and I run,</p> <p>N. 89° 54' E. on a true line along the N. Bdy. of Sec. 6</p> <p style="text-align: right;">Var. 20° 15' E.</p> | |
| 39.53 | <p>Set basalt stone 16 x 10 x 8 on E. slope for $\frac{1}{4}$ Sec. Cor.</p> <p style="padding-left: 40px;">A Pine 28 ins. diam. brs. N. 27° W. 30 lks. dist.</p> <p style="padding-left: 80px;">" " 12 " " " S. 42° E. 25 " "</p> | |
| 79.53 | <p>Set basalt stone 15 x 10 x 8 and post in mound of stone on E. slope for Cor. to Secs. 5, 6, 31 and 32.</p> <p>No trees.</p> <p>Land; surface rolling and sloping E.</p> <p>Soil; 2nd and 3rd rate, some scattering groves of timber Pine, Tamarack and Fir. Mostly open. Good grass.</p> <p>Some good farming land.</p> | |
| | <p>N. 89° 54' E. on a true line along the N. Bdy of Sec. 5</p> <p style="text-align: right;">Var. 21° 15' E</p> | |
| 40.00 | <p>Set Basalt. stone 18 x 14 x 10 in mound of stone on N.E. slope for $\frac{1}{4}$ Sec. Cor.</p> <p style="padding-left: 40px;">A Pine 10 ins. diam. brs. N. 38° E. 64 lks. dist.</p> <p>No tree on S. side.</p> | |
| 52.50 | <p>A ravine, course S.E. and N.W.</p> | -200 |
| 80.00 | <p>Set basalt stone 18 x 12 x 6 and post in mound of stone for Cor. to Sec. 4, 5, 32 and 33. No trees.</p> <p>Land; surface rolling and sloping E.</p> <p>Soil; 2nd and 3rd rate. Scattering groves of Pine and Tamarack timber. Good grass. Some good farming land.</p> | |